BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/03/2014-15 Dated: 07-10-2014

APPROVED TENDER SCHEDULE –'B'

Item No: 2

Name of Work:-Construction of concrete roads to Sihi Neeru Rasthe and RCC drain at Kanakanagara in ward No:04 of Yelahnka satellite town sub division.

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri R SATHEESH	
				Rate	Rate in Words
1					Rupees one thousand ten only
1	KSRRB 300-1:Earthwork excavtion by manual means in ordinary soil involving an average horizontal throw upto 2 Meters and an average lift upto 0.5m excavated surface leveled and sides neatly dressed the disposed earth to be levelled neatly after breaking of clods complete as per specifications and complete as per specifications.with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Cum	59.76	60.00	Rupees sixty only
2	KSRB 2-2.2 : Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m , in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. [illegible]	Cum	56.98	220.00	Rupees two hundred twenty only
3	KSRRB 300-45 Scarifying stone metal crust 50mm to 100 mm thick with pick axes along with premix carpet/surface dressing and stacking of old serviceable materials within a lead of 100 meters by manual means including cost of all labour charges complete as per specifications MORTH chapter.3 with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Sqm	722.30	40.00	Rupees forty only
4	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M 7.5 withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification with all lead and lift complete asper specification as per direction of Engineer incharges	Cum	120.63	4100.00	Rupees four thousand one hundred only

For Bruhat Bangalore Mahanagara Palike

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri R SATHEESH	
				Rate	Rate in Words
5	KSRB 4.2.2 : Providing and laying in position Reinforced cement concrete of mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum with superplastesisre @ 3lts conforming to IS9103-1999Reffirmed machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications. Specification.	Cum	15.51	5630.00	Rupees five thousand six hundred thirty only
6	Providing and laying cement concrete using 20mm and down size granite jelly or ready mixed concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing and necessary steel or ply wood or plank centering and form work etc., including smooth finish in CM 1:3, with all lead and lift etc., complete. (exculsive of cost of steel and fabrication charges)	Cum	381.74	5300.00	Rupees five thousand three hundred only
7	KSRB 4.9.2:Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications.Specification	Qtl	15.51	7000.00	Rupees seven thousand only
8	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, attached pilasters,bittresses,buttresses plinth and sriag course including cost of all materials, labour complete as per specifications. Specification	Sqm	220.50	270.00	Rupees two hundred seventy only
9	Providing and fixing Precast RCC Slabs as Per approved design, specification and Direction Engineer-in-Charge. (Approved Data Rate).	Sqm	102.30	1100.00	Rupees one thousand one hundred only
10	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 7.00 Km	Cum	116.74	80.00	Rupees eighty only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.